

Stora Enso Hylte Mill

Hylte, Sweden

Factory within the existing mill to produce Molded Fiber.

Construction time 4-4,5 months from delivery to finished MEP.

Measurements 25*25*5,8

CLT VI 145 m³ and 490 m² CLT Rib panels



General

Delivery year

2019

Building type

Industrial

Area (m²)

900




Photo credit: Stora Enso



Products

Products

CLT, CLT rib panel

Product quality

VI

Product volume (m³)

195



Photo credit: Stora Enso



 **Team**

Developer
Stora Enso

Structural Engineer
Sweco Structures

Main contractor
AF Bygg SYD

Architect
Sweco Architects AB

MEP Designer
Sweco

Specialist Timber Contractor
AF Bygg SYD




Photo credit: Stora Enso

 **Others**

Construction duration (months)
2

Timber superstructure erection duration (weeks)
2